VE
C 1

UNITED STATES MARINE CORPS

MATERIEL REFERENCE DATA FOR LOADING AND STOWING

NAVMC 1021 DPP

Change #1. MH 12 Feb.
Change #2. MH 12 Feb.
O.T. Chart Added.

MARINE CORPS HISTORICAL LIBRARY

MARINE CORPS HISTORICAL LIBRARY
HQMC ROOM 3127

DIRECTOR [illegible]

UNITED STATES MARINE CORPS

MATERIEL REFERENCE DATA FOR LOADING AND STOWING

APPROVED 10 JANUARY 1945:

A A Vandegrift

COMMANDANT OF THE MARINE CORPS

DISTRIBUTION "Z"

6332

UNITED STATES MARINE CORPS

MATERIEL REFERENCE DATA FOR LOADING AND STOWING

1. Purpose—This volume provides loading and stowing data on Marine Corps materiel such as engineer equipment, ordnance equipment, tractors, trailers, trucks, and miscellaneous equipment requiring special consideration in loading and stowing.

2. Photographs—Photographs are not to scale. They are intended simply to give an idea of the general appearance of each item of equipment.

3. Sketches—Sketches are drawn to the scale of one eighth inch equals one foot (⅛″ = 1′) and may be used in connection with diagrams provided in Ship's Characteristics. Prominent indentations and protrusions are shown in the sketches so that this information can be utilized in planning the stowage of cargo.

4. Dimensions—All dimensions are shown in feet and inches and are actual measurements.

5. Stowage Requirements—The figures given under "Stowage Requirements" on the data sheets provide actual cubic feet of hold space and actual square feet of deck space which must be allowed each item of equipment in computing shipping requirements. No broken stowage is included in these figures.

6. This publication supercedes the volume "Marine Corps Materiel Reference Data For Loading and Stowing—1943".

VE
153
.A46L5
1945
c.1

MATERIEL REFERENCE DATA FOR LOADING AND STOWING

●

INDEX

●

ENGINEER

ITEM OF EQUIPMENT — PAGE NO.
Camera, Copying, 24" x 24", Trailer-Mounted 1
Compressor, Air, 55 Cu. Ft. Capacity, 2-Wheel 2
Compressor, Air, (Davey), Gasoline Powered, Trailer-Mounted (ANV) 3
Compressor, Air, 60 Cu. Ft., 2-Wheel, Trailer-Mounted 4
Compressor, Air, 105 Cu. Ft., 4-Wheel, Trailer-Mounted 5
Crane, 15-20 Ton, 2-Wheel, (LeTourneau) 6
Crusher, Rock, Gasoline Engine Powered, 4-Wheel 7
Crusher, Rock, Gasoline, Portable, (10 x 20 Jaw Crusher) 8
Crushing Plant, Rock, Diesel, Portable, (Primary Unit) (20' Elevators) 9
Crushing Plant, Rock, Diesel, Portable, (Secondary Unit) (Hopper's) 10
Cultivator, Tractor-Operated 11
Darkroom, Lithograhic, Trailer-Mounted 12
Darkroom, Photographic, Trailer-Mounted 13
Distillation ~~Plant~~ Unit, 1500 Gal. per Day Capacity, 4-Wheel 14
Distributor, Asphalt Emulsion, 800 Gal., Trailer-Mounted 15
Truck, 2-1/2 Ton, 6x6, Tank Pressure Distributor, 1000 Gal.
~~Distributor, Asphalt, Pressure Type, 1000 Gal., Truck-Mounted~~ 16
Earth Auger, Self-Powered & Self-Propelled, 4-Wheel 17
Generator, Electric, 3 KVA, 60 Cycle, 1 Phase 18
Generator, Electric, 6.25 KVA, Portable 19
Generator, Electric, 7.5 KVA, Portable, Trailer-Mounted 20
Generator, Electric, 9.4 KVA, Trailer-Mounted 21
Generator, Electric, 10 KW, (Consolidated) (AVN) 22
Generator, Electric, Diesel Engine Driven, 30 KW, Trailer-Mounted 23
Grader, Road, Leaning Wheel Type, 4-Wheel 24
Grader, Road, ~~Self-Propelled, W/Scarifier~~ Motor Driven, Diesel Engine, V/Type Scarifier 25
Harrow, Spike Tooth, 10' Wide, Tractor Drawn 26
Harrow, Disc, Tractor Drawn 27
Kettle, Tar & Asphalt, 110 Gal. Capacity 28
Mixer, Concrete, 14 Cu. Ft. Capacity, 4-Wheel 29
Mixer, Road Material 30
Plow, 4-Furrow, 16" Moldboard 31
Plow, Grading 32
Press, Lithographic, Trailer-Mounted 33
Pump, Centrifugal, 3", Gasoline Engine Powered 34
Pump, Water Double Diaphragm, 3", Gasoline Engine Powered 35
Pumping Set, Centrifugal, 55 Gal. per Minute 36
Rig, Well, Self-Powered, 4-Wheel 37
Ripper, Cable-Operated, 2-Wheel 38
Roller, Wheeled, Rubber-Tired 39
Roller, Tamping, Sheepsfoot, Dual Drum 40
Roller, Tandem, 5-Ton, Diesel 41
Roller, Smooth, 10-Ton, Diesel 42
Scraper, 2-Wheel, Back Dumping, 3½ Cu. Yd. 43
Scraper, 4-Wheel, Front Dumping, 1½ Cu. Yd. 44
Scraper, Road, Wagon Type, Complete, 4-Wheel ~~4-Wheel, Front Dumping, 8 Cu. Yd.~~, Cable Operated, 8 cu. yd. Capacity 45

MATERIEL REFERENCE DATA FOR LOADING AND STOWING

●

ENGINEER (CONTINUED)

ITEM OF EQUIPMENT PAGE NO.

Shovel, Gasoline, Motorized, 3/8 Cu. Yd., Capacity 46
  Dragline Bucket, F/3/8 Cu. Yd. Shovel 47
  Pile Driver, Slide & Hammer, F/3/8 Cu. Yd. Shovel 48
  Trench Hoe Bucket, F/3/8 Cu. Yd. Shovel 49
  Trench Hoe Mast, F/3/8 Cu. Yd. Shovel 50
Shovel, 3/4 Cu. Yd., Capacity 51
  Clamshell Bucket, F/3/4 Cu. Yd. Shovel 52
  Crane Boom, F/3/4 Cu. Yd. Shovel 53
  Dragline Bucket, F/3/4 Cu. Yd. Shovel 54
  Dipper Stick, Boom, Bucket, F/3/4 Cu. Yd. Shovel 55
  Pile Driver Conversion Unit, F/3/4 Cu. Yd. Shovel 56
Sprayer, Paint, Camouflage, Trailer-Mounted 57
Steriliation & Bath Unit, Mobile 58
Trailer, 4 Ton, 4-Wheel, Tank 800 Gal; F/asphalt Emulsion Distributor
~~Tank, Service, Asphalt Emulsion, 800 Gal.~~ 59
Trencher, Rotary Wheel 60
Water Purification Unit, Portable 61
Water Purification Filter, Portable 61
Welder, 200 Amp., Gasoline Engine Driven 62
Welder, 300 Amp., Gasoline Engine Driven (Lincoln) 63
Welder, 300 Amp., Gasoline Engine Driven (P&H) 64
Winch, Diesel Operated, Complete 65

ORDNANCE

Amphibian Tractor, LVT (2) or (A2) 66
Amphibian Tractor, LVT (3) 67
Amphibian Tractor, LVT (4) 68
Armored Amphibian, (LVT (A) (4)) 69
Carriage, Motor, 105-mm, M7 or M7B1, W/Armament 70
Finder Height, 13½ Ft., M1A1, Complete, W/Cradle 71
Generating Unit, M7, W/Trailer M-7 or M7A1 72
Gun, 20MM, Antiaircraft, MK IV 73
Gun, 37MM, Antitank 74
Gun, Automatic, 40MM, M1 75
Gun, Motor Carriage, 75MM, M3, W/Armament 76
Gun, 90MM, AA, M1 77
Gun, 155MM, M1 or M1A1 78
Howitzer, Pack, 75-MM, M1A1, Carriage M1 79
Howitzer, 105MM, M2A1 80
Howitzer, 155MM, M1 81
Power Unit, F/Searchlight 82
Projector, Target, Rocket, M1 83
Searchlight, AA, 60", Mobile Unit 84
Tank, Medium, M4A2 or M4A3, W/Bulldozer TANK Mounting 84N
Tank, Medium, M4A2 or M4A3, W/75MM Gun 85
Tank, Medium, M4A3, W/105MM Howitzer 86
Vehicle, Tank Recovery, M32B2 or M32B3, W/Armament 87

TRACTORS

Tractor, Light, TD-9 W/Athey Mobile Loader 88
Tractor, MG1 or MG2, Cletrac (AVN) 89

●

TRACTORS (CONTINUED)

ITEM OF EQUIPMENT PAGE NO.
Tractor, ~~Medium~~ Light, TD-9 90
Tractor, ~~Medium,~~ Light, TD-9 W/Angledozer 91
Tractor, ~~Medium,~~ Light, TD-9 W/Dozer Shovel 92
Tractor, Medium, TD-14 W/Power Control Unit 93
Tractor, ~~Medium~~ Light, TD-9, W/TV-9 Crane 94
Tractor, Heavy, T.D.-18, W/power Control Unit 95
Tractor, ~~Heavy,~~ Medium, TD-14 Armored 96
Tractor, ~~Heavy,~~ Medium, TD-14 W/Angledozer 97
Tractor, Heavy, TD-18, W/Angledozer ~~W/Bullgrader~~ 98
Tractor, ~~Heavy,~~ Medium, TD-14 W/Bull Clamshovel 99
Tractor, Heavy, TD-18 W/Front End Winch 100
Tractor, ~~Heavy, W/Roustabout Crane, 360° Traverse~~ Medium, TD-14, W/Hughes Keenan MC-2R CRANE 101
Tractor, Heavy, 4-Wheel, W/Heil Crane 102
Tractor, Heavy, TD-18 W/Double Drum Power Take-off 103
Tractor, Heavy, TD-18 W/Power Control Unit 104
Tractor, Light Farmall, ~~W~~ H/Rubber Tires ~~or Metal Wheels~~ General Purpose 105
Tractor, Wheel, 3½ Ton, 4 x 4, (AVN) 106

TRAILERS

Trailer, ¼-Ton, 2-Wheel, Cargo 107
Trailer, ½-Ton, 2-Wheel, Dump 108
Trailer, 1-Ton, 2-Wheel, Cargo 109
Trailer, 1-Ton, 2-Wheel, Greasing 110
Trailer, 1-Ton, 2-Wheel, High Pressure Cleaning Unit 111
Trailer, 1-Ton, 2-Wheel, K-52, (PE-95) 112
Trailer, 1-Ton, 2-Wheel, Radio (AVN) 112
Trailer, 1-Ton, 2-Wheel, Stockroom 113
Trailer, 1-Ton, 2-Wheel, Water, 300 Gal. 114
Trailer, 2-Ton, 4-Wheel, AA, Searchlight 115
Trailer, 2-Ton, 4-Wheel, Platform, 12′ 116
Trailer, 2-Ton, 4-Wheel, Platform, 15′ 117
Trailer, 2-Ton, 4-Wheel, Power Unit (F/Radar Set SK-1M, SP-1M, & Mark 33) 118
Trailer, 2-Ton, 4-Wheel, Stockroom 119
Trailer, 3-Ton, 4-Wheel, Instrument 120
Trailer, 5-Ton, 4-Wheel, Photographic Equipment: Reproduction Equipment 120N
Trailer, 3-Ton, 4-Wheel, Water Purification Unit 121
Trailer, 3-Ton, Cargo, Track-laying 122
Trailer, 3~~½~~-Ton, 2-Wheel, Cargo ~~Carrier, Watertight~~ Amphibian Trailer 2 wheel Med. Amp. 123
Trailer, 5-Ton, 4-Wheel, Machine Shop No. 1 124
Trailer, 5-Ton, 4-Wheel, Machine Shop No. 2 125
Trailer, 5-Ton, 4-Wheel, Ponton Balk, W/Bolster 126
Trailer, 5-Ton, 4-Wheel, Ponton Balk, W/O Bolster 127
Trailer, Pole, 2-Wheel, Ponton, Balk 128
Trailer, 5-Ton, 4-Wheel, (SKD-2226) (Radio Intelligence) 129
Trailer, 6-Ton, Cargo, Track-laying 130
Trailer, 6-Ton, 26′ Semi-Stake, W/Detachable Front Bogie 131
Trailer, 7-Ton, 6-Wheel, (Operating) (F/Radar Set SP-1M) 132
Trailer, 7-Ton, 6-Wheel, (Equipment) (F/Radar Set SP-1M) 133

●

TRAILERS (CONTINUED)

ITEM OF EQUIPMENT PAGE NO.

Trailer, 7-Ton, 4-Wheel, (Power) (F/Radio Set SCR 270-(B) (Navy) or SCR-270(D) (Navy)) 134
Trailer, 8-Ton, 6-Wheel, (Operating) (F/Radar Set SK-1M) 135
Trailer, ~~10~~ 6-Ton, Semi-Trailer, 2-Wheel, Van Type Laundry 136
Trailer, 11-Ton, 4-Wheel, (Operating) (F/Radio Set SCR-270(B) (Navy) or SCR-270(D) (Navy)) 137
Trailer, 13-Ton, 4-Wheel, (Antenna) (F/Radio Set SCR-270(B) (Navy) or SCR-270(D) (Navy)) 138
Trailer, 15-18-Ton, Machinery 139
Trailer, 16-Ton, 4-Wheel, Low Bed 140
Trailer, 20-Ton, Drop Frame (AVN) 141
Trailer, 25-Ton, Low Bed Semi-Trailer 142
Trailer, 45-Ton, 12 Wheel, M9 142-N
Trailer, Bomb, Mark I, (AVN) 143
Trailer, Bomb, Mark II, (AVN) 144
Trailer, Bomb, Mark V, (AVN) 145
Trailer, Cable Splicer, ~~Telephone, ¼-Ton,~~ K-38 146
Trailer, Camp Lighting, 110 AC, 10 KVA, (AVN) 147
Trailer, Chrysler, Fire Fighting 148
Trailer, Combination Cable Reel & Pole, K-37 149
Trailer, Fire & Decontamination (AVN) 150
Trailer, Dolly Converter, F/Trailer, Gasoline, 3200 Gal. (AVN) 151
Trailer, Gasoline, 2000 Gal. Capacity (AVN) 152
Trailer, Gasoline, 3200 Gal. Capacity, W/Dolly (AVN) 153
Trailer, Mobile Hospital Operating Room 153-N
Trailer, Oil Refiner 154
Trailer, Photographic (AVN) 155
Trailer, Pole Hauling ~~& Cargo,~~ K-36 156
Trailer, Power, F/Radio & Radar Repair Truck 157
Trailer, 2-Wheel, Shower Unit, 24 Head 158
Trailer, 1-Ton, 2-Wheel, Steam Jenny (Kerrick Kleaner) (AVN) 159

TRUCKS

Ambulance, ¼-Ton, 4 x 4 160
Ambulance, ½-Ton, 4 x 4 161
Car, 5-Passenger (Chevrolet) 162
Carrier, Personnel, Half-Track, M-3, Radio-Equipped 163
Station Wagon ~~Carryall, 8-Passenger,~~ 4 x 4 164
Station Wagon, 4 x ~~4~~ 2 165
Truck, ¼-Ton, 4 x 4 166
Truck, ½-Ton, 4 x 2, Pick-up, ~~(Base Depot)~~ 167
Truck, ¾-Ton, 4 x 4, Weapons Carrier 168
Truck, 1-Ton, 4 x 4, (Cargo) 169
Truck, 1-Ton, 4 x 4, Light Repair 169
Truck, 1-Ton, 4 x 4, Reconnaissance 169
Truck, 1-Ton, Greasing 170
Truck, 1½-Ton, Cargo (AVN) 171
Truck, 1½-Ton, 4 x 2, Fire, 500 Gal. 172
Truck, 1½-Ton, 4 x 4, K-51 (F/SCR-299) 173
Truck, 1½-Ton, 4 x 4, Radio (AVN) 173
Truck, 1½-Ton, 6 x 6, Cargo 174

MATERIEL REFERENCE DATA FOR LOADING AND STOWING

●

TRUCKS (CONTINUED)

ITEM OF EQUIPMENT PAGE NO.
Truck, 2½-Ton, 4 x 4, Cargo (Prime Mover) 175
Truck, 2½-Ton, 6 x 6, Amphibian 176
Truck, 2½-Ton, 6 x 6, Artillery Repair, M9A1, W/Load A 177
Truck, 2½-Ton, 6 x 6, Automobile Repair, M8A1, W/Load A 177
Truck, 2½-Ton, 6 x 6, Cargo 178
Truck, 2½-Ton, 6 x 6, Dump 179
Truck, 2½-Ton, 6 x 6, Electric Repair, M12A1, W/Load 177
Truck, 2½-Ton, 6 x 6, Instrument Bench, M23A1, W/Load 177
Truck, 2½-Ton, 6 x 6, Instrument Repair, M10A1, W/Load A 177
Truck, 2½-Ton, 6 x 6, Machine Shop, M16A1, W/Load A 177
Truck, 2½-Ton, 6 x 6, Photographic Repair 180
Truck, 2½-Ton, 6 x 6, Radio & Radar Repair (AVN) 181
Truck, 2½-Ton, 6 x 6, Signal Repair M-30 181
Truck, 2½-Ton, 6 x 6, Small Arms Repair, M7A1, W/Load A 177
Truck, 2½-Ton, 6 x 6, Stake 182
Truck, 2½-Ton, 6 x 6, Tank, Gasoline, 750 Gal. 183
Truck, 2½-Ton, 6 x 6, Telephone Construction & Maintenance 184
Truck, 2½-Ton, 6 x 6, W/Ordnance Maintenance Set "F", (Artillery Repair) 177
Truck, 2½-Ton, 6 x 6, Welding, W/Maintenance Load L, (Welding Truck) 177
Truck, Tractor, 4 x 2~~, K-10~~. 185
Truck, Tractor, 2½-Ton, 6 x 6 186
Truck, 2½-Ton, 6 x 6, Wrecking 187
Truck, 3-Ton, 6 x 6, Dump (AVN) 188
Truck, 12-Ton, Low Bed, Stake Body 189
Truck, 12-Ton, 6x4, M20 189N
Truck, 4 x 4, Bomb Service, Mark II (AVN) 190
Truck, 4 x 4, Gasoline, 600 Gal. (International) (AVN) 191
Truck, Fire & Rescue (International) (AVN) 192
Truck-Tractor, W/Crane (Autocar) (AVN) 193
Truck-Tractor, W/Crane (Oshkosh) (AVN) 194

MISCELLANEOUS

Apparatus, Decontaminating, Power Driven, M-4 195
Cabinet, Fumigation, Methyl Bromide 196
Cargo Carrier, M29-C, Amphibious 196N
Crane, 10-Ton, Truck Mounted 197
PALLET 197N
Repair Unit, 4-Ton, 4-Wheel, Shoe & Textile, 2000 Men (Trailer Mounted) 198
Truck, 4000-LB., Fork, Plane Loader (AVN) 199
Truck, 6000-LB., Fork Lift, Warehousing 200

ENGINEER
EQUIPMENT

CAMERA, Copying, 24" x 24", Trailer-Mounted





| SCALE: 1/8" = 1'

DIMENSIONS:	
Length	19' 10"
Width	8'
Height	9' 6"
STOWAGE REQUIREMENTS:	
Square Feet	158
Cubic Feet	1,505
WEIGHT:	
Pounds	9,930

COMPRESSOR, Air 55 Cu. Ft. Capacity, 2-Wheel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	4' 4"
Width	4' 2"
Height	3' 10"
STOWAGE REQUIREMENTS:	
Square Feet	18
Cubic Feet	69
WEIGHT:	
Pounds	1,180

COMPRESSOR, Air (Davey), Gas Powered, Trailer-Mounted (AVN)





SCALE: 1/8" = 1'   3

DIMENSIONS:	
Length	**13'**
Width	**5' 8"**
Height	**6' 3"**
STOWAGE REQUIREMENTS:	
Square Feet	**75**
Cubic Feet	**469**
WEIGHT:	
Pounds	**3,450**

COMPRESSOR, Air, 60 Cu. Ft., 2-Wheel, Trailer-Mounted





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**7' 1"**
Width	**4' 11"**
Height	**5'**
STOWAGE REQUIREMENTS:	
Square Feet	**35**
Cubic Feet	**175**
WEIGHT:	
Pounds	**2,055**

COMPRESSOR, Air, 105 Cu. Ft., 4-Wheel, Trailer-Mounted





DIMENSIONS:

Length	13'
Width	5' 4"
Height	5' 10"

STOWAGE REQUIREMENTS:

Square Feet	69
Cubic Feet	400

WEIGHT:

Pounds	7,480

CRANE, 15-20 Ton, 2-Wheel (LeTourneau)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	42' 10"
Width	9' 2"
Height	5'
STOWAGE REQUIREMENTS:	
Square Feet	394
Cubic Feet	492
WEIGHT:	
Pounds	5,000

CRUSHER, Rock, Gasoline Engine Powered, 4-Wheel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10' 1"
Width	5' 10"
Height	6' 10"
STOWAGE REQUIREMENTS:	
Square Feet	59
Cubic Feet	398
WEIGHT:	
Pounds	9,250

CRUSHER, Rock, Gasoline, Portable
(10 x 20 Jaw Crusher)





SCALE: 1/8" = 1'

DIMENSIONS:

Length	**10' 2"**
Width	**5' 10"**
Height	**6' 10"**

STOWAGE REQUIREMENTS:

Square Feet	**59**
Cubic Feet	**398**

WEIGHT:

Pounds	**9,250**

CRUSHING PLANT, Rock, Diesel, Portable (Primary Unit) (20′ Elevators)





SCALE: 1/8″ = 1′

DIMENSIONS:	
Length	23′
Width	10′ 4″
Height	13′ 2″
STOWAGE REQUIREMENTS:	
Square Feet	237
Cubic Feet	3,245
WEIGHT:	
Pounds	28,900

CRUSHING PLANT, Rock, Diesel, Portable (Secondary Unit) (Hopper's)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	19' 7"
Width	10' 4"
Height	13'
STOWAGE REQUIREMENTS:	
Square Feet	202
Cubic Feet	2,626
WEIGHT:	
Pounds	36,060

CULTIVATOR, Tractor-Operated





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	9' 1"
Width	8' 6"
Height	3'
STOWAGE REQUIREMENTS:	
Square Feet	77
Cubic Feet	232
WEIGHT:	
Pounds	2,111

DARKROOM, Lithographic, Trailer-Mounted





DIMENSIONS:	
Length	**15' 4"**
Width	**8' 2"**
Height	**9' 8"**
STOWAGE REQUIREMENTS:	
Square Feet	**126**
Cubic Feet	**1,217**
WEIGHT:	
Pounds	**7,720**

DARKROOM, Photographic, Trailer-Mounted





DIMENSIONS:

Length	**15' 4"**
Width	**8' 2"**
Height	**9' 8"**

STOWAGE REQUIREMENTS:

Square Feet	**126**
Cubic Feet	**1,217**

WEIGHT:

Pounds	**7,650**

DISTILLATION ~~PLANT~~ UNIT, 1,500 Gal. per Day Capacity, 4-Wheel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**12' 4"**
Width	**7' 2"**
Height	**6' 2"**
STOWAGE REQUIREMENTS:	
Square Feet	**90**
Cubic Feet	**558**
WEIGHT:	
Pounds	**4,970**

DISTRIBUTOR, Asphalt Emulsion, 800 Gal., Trailer-Mounted





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	15' 7"
Width	7' 10"
Height	7' 10"
STOWAGE REQUIREMENTS:	
Square Feet	122
Cubic Feet	950
WEIGHT:	
Pounds	9,830

TRUCK, 2-½ TON, 6x6, tank Pressure Distributor,

~~DISTRIBUTOR, Asphalt, Pressure Type, 1000 Gal., Truck-Mounted~~

1000 Gal.





SCALE: 1/8" - 1'

DIMENSIONS:	
Length	22' 6"
Width	7' 6"
Height	8'
STOWAGE REQUIREMENTS:	
Square Feet	169
Cubic Feet	1,350
WEIGHT:	
Pounds	12,990

EARTH AUGER, Self-Powered & Self-Propelled, 4-Wheel





DIMENSIONS:	
Length	19'
Width	6' 5"
Height	6'
STOWAGE REQUIREMENTS:	
Square Feet	122
Cubic Feet	732
WEIGHT:	
Pounds	6,560

GENERATOR, Electric, 3 KVA, 60 Cycle, 1 Phase





DIMENSIONS:

Length	3' 11"
Width	2' 10"
Height	2' 10"

STOWAGE REQUIREMENTS:

Square Feet	11
Cubic Feet	31

WEIGHT:

Pounds	715

GENERATOR, Electric, 6.25 KVA, Portable





SCALE: 1/8"= 1'

DIMENSIONS:	
Length	5' 8"
Width	2' 8"
Height	4' 1"
STOWAGE REQUIREMENTS:	
Square Feet	15
Cubic Feet	63
WEIGHT:	
Pounds	1,135

GENERATOR, Electric, 7.5 KVA, Portable, Trailer-Mounted





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**10' 10"**
Width	**5' 8"**
Height	**6' 4"**
STOWAGE REQUIREMENTS:	
Square Feet	**62**
Cubic Feet	**388**
WEIGHT:	
Pounds	**2,850**

GENERATOR, Electric, 9.4 KVA, Trailer-Mounted





SCALE: 1/8" 1'

DIMENSIONS:	
Length	**8' 10"**
Width	**5' 5"**
Height	**5' 6"**
STOWAGE REQUIREMENTS:	
Square Feet	**48**
Cubic Feet	**261**
WEIGHT:	
Pounds	**2,730**

GENERATOR, Electric, 10 KW (Consolidated) (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**9' 3"**
Width	**5' 2"**
Height	**5' 7"**
STOWAGE REQUIREMENTS:	
Square Feet	**48**
Cubic Feet	**268**
WEIGHT:	
Pounds	**2,000**

GENERATOR, Electric, Diesel Engine Driven, 30 KW, Trailer-Mounted





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**9′ 4″**
Width	**5′ 10″**
Height	**6′ 11″**
STOWAGE REQUIREMENTS:	
Square Feet	**54**
Cubic Feet	**373**
WEIGHT:	
Pounds	**7,250**

GRADER, Road, Leaning Wheel Type, 4-Wheel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	33′
Width	9′ 7″
Height	7′ 5″
STOWAGE REQUIREMENTS:	
Square Feet	317
Cubic Feet	2,345
WEIGHT:	
Pounds	12,300

Motor Driven, Diesel Engine

GRADER, Road, ~~Self-Propelled, W/Scarifier~~

V/Type Scarifier.





DIMENSIONS:	
Length	**24' 4"**
Width	**8'**
Height	**7' 10"**
STOWAGE REQUIREMENTS:	
Square Feet	**195**
Cubic Feet	**1,517**
WEIGHT:	
Pounds	**20,000**

HARROW, Spike Tooth, 10' Wide, Tractor Drawn





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10' 4"
Width	1' 2"
Height	1' 2"
STOWAGE REQUIREMENTS:	
Square Feet	12
Cubic Feet	15
WEIGHT:	
Pounds	150

HARROW, Disc, Tractor Drawn





DIMENSIONS:	
Length	**12'**
Width	**8' 4"**
Height	**2' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**100**
Cubic Feet	**239**
WEIGHT:	
Pounds	**2,000**

KETTLE, Tar & Asphalt, 110 Gal. Capacity





DIMENSIONS:	
Length	9' 1"
Width	4' 10"
Height	4'
STOWAGE REQUIREMENTS:	
Square Feet	44
Cubic Feet	176
WEIGHT:	
Pounds	1,200

MIXER, Concrete, 14 Cu. Ft. Capacity, 4-Wheel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	8' 7"
Width	9' 2"
Height	10' 4"
STOWAGE REQUIREMENTS:	
Square Feet	79
Cubic Feet	814
WEIGHT:	
Pounds	5,580

MIXER, Road Material





SCALE: 1/8" - 1'

DIMENSIONS:	
Length	16' 5"
Width	6' 10"
Height	6' 6"
STOWAGE REQUIREMENTS:	
Square Feet	112
Cubic Feet	725
WEIGHT:	
Pounds	4,850

PLOW, 4-Furrow, 16" Moldboard





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**14' 7"**
Width	**7'**
Height	**4'**
STOWAGE REQUIREMENTS:	
Square Feet	**102**
Cubic Feet	**409**
WEIGHT:	
Pounds	**1,380**

PLOW, Grading




2'7"
8'6"
SCALE 1/8" = 1'

DIMENSIONS:	
Length	8′ 6″
Width	2′ 7″
Height	2′ 8″
STOWAGE REQUIREMENTS:	
Square Feet	22
Cubic Feet	59
WEIGHT:	
Pounds	340

PRESS, Lithographic, Trailer-Mounted





Scale 1/8" = 1'

DIMENSIONS:	
Length	15' 4"
Width	8'
Height	9' 6"
STOWAGE REQUIREMENTS:	
Square Feet	122
Cubic Feet	1,163
WEIGHT:	
Pounds	9,930

PUMP, Centrifugal, 3", Gasoline Engine Powered





DIMENSIONS:	
Length	4' 10"
Width	2' 5"
Height	3' 7"
STOWAGE REQUIREMENTS:	
Square Feet	12
Cubic Feet	42
WEIGHT:	
Pounds	1,004

PUMP, Water Double Diaphragm, 3", Gasoline Engine Powered





SCALE 1/8" = 1'

DIMENSIONS:	
Length	**6' 4"**
Width	**3' 1"**
Height	**3' 10"**
STOWAGE REQUIREMENTS:	
Square Feet	**20**
Cubic Feet	**74**
WEIGHT:	
Pounds	**1,025**

PUMPING SET, Centrifugal, 55 Gal. per Minute





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**2' 5"**
Width	**1' 10"**
Height	**2' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**4**
Cubic Feet	**10**
WEIGHT:	
Pounds	**198**

RIG, Well, Self-Powered, 4-Wheel





DIMENSIONS:	
Length	22′
Width	8′ 1″
Height	8′ 8″
STOWAGE REQUIREMENTS:	
Square Feet	178
Cubic Feet	1,550
WEIGHT:	
Pounds	8,850

RIPPER, Cable-Operated, 2-Wheel





DIMENSIONS:

Length	13'
Width	6' 11"
Height	4' 5"

STOWAGE REQUIREMENTS:

Square Feet	90
Cubic Feet	396

WEIGHT:

Pounds	6,010

ROLLER, Wheeled, Rubber-Tired





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	5' 4"
Width	5' 4"
Height	3' 7"
STOWAGE REQUIREMENTS:	
Square Feet	28
Cubic Feet	101
WEIGHT:	
Pounds	4,000

ROLLER, Tamping, Sheepsfoot, Dual Drum


BUCYRUS
ERIE



SCALE: 1/8" = 1'

DIMENSIONS:	
Length	13′ 5″
Width	9′ 4″
Height	4′ 6″
STOWAGE REQUIREMENTS:	
Square Feet	127
Cubic Feet	572
WEIGHT:	
Pounds	6,480

ROLLER, Tandem, 5-Ton, Diesel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	14' 7"
Width	5' 4"
Height	7' 5"
STOWAGE REQUIREMENTS:	
Square Feet	78
Cubic Feet	573
WEIGHT:	
Pounds	11,750

ROLLER, Smooth, 10-Ton, Diesel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20' 4"
Width	7'
Height	8' 1"
STOWAGE REQUIREMENTS:	
Square Feet	142
Cubic Feet	1,151
WEIGHT:	
Pounds	28,000

SCRAPER, 2-Wheel, Back Dumping, 3-1/2 Cu. Yd.


BUCYRUS
ERIE



Scale-1/8"=1'

DIMENSIONS:

Length	13′ 6″
Width	9′ 4″
Height	4′ 7″

STOWAGE REQUIREMENTS:

Square Feet	126
Cubic Feet	577

WEIGHT:

Pounds	6,600

SCRAPER, 4-Wheel, Front Dumping, 1-1/2 Cu. Yd.





Scale-1/8"=1'

DIMENSIONS:

Length	12' 4"
Width	5' 6"
Height	4' 5"

STOWAGE REQUIREMENTS:

Square Feet	68
Cubic Feet	298

WEIGHT:

Pounds	2,400

Road, Wagon Type, Complete

SCRAPER, 4-Wheel, ~~Front Dumping, 8 Cu. Yd.,~~
Cable-Operated

8 Cu. Yd. Capacity





DIMENSIONS:

Length	20′ 4″
Width	9′ 4″
Height	9′

STOWAGE REQUIREMENTS:

Square Feet	189
Cubic Feet	1,700

WEIGHT:

Pounds	17,000

SHOVEL, Gasoline, Motorized, 3/8 Cu. Yd. Capacity





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**12' 5"**
Width	**7' 10"**
Height	**9' 6"**
STOWAGE REQUIREMENTS:	
Square Feet	**97**
Cubic Feet	**919**
WEIGHT:	
Pounds	**18,000**

DRAGLINE BUCKET, F/3/8 Cu. Yd. Shovel





Scale-1/8" = 1'

DIMENSIONS:	
Length	**4' 7"**
Width	**3' 10"**
Height	**2' 10"**
STOWAGE REQUIREMENTS:	
Square Feet	**18**
Cubic Feet	**49**
WEIGHT:	
Pounds	**1,080**

PILE DRIVER, Slide & Hammer, F/3/8 Cu. Yd. Shovel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	13'
Width	2' 4"
Height	3' 2"
STOWAGE REQUIREMENTS:	
Square Feet	30
Cubic Feet	96
WEIGHT:	
Pounds	3,600

TRENCH HOE BUCKET, F/3/8 Cu. Yd. Shovel





SCALE 1/8" = 1'

DIMENSIONS:	
Length	**9' 7"**
Width	**3' 10"**
Height	**2' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**37**
Cubic Feet	**90**
WEIGHT:	
Pounds	**1,850**

TRENCH HOE MAST, F/3/8 Cu. Yd. Shovel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	9'
Width	1' 7"
Height	1'
STOWAGE REQUIREMENTS:	
Square Feet	14
Cubic Feet	14
WEIGHT:	
Pounds	900

SHOVEL, 3/4 Cu. Yd. Capacity





SCALE: 1.8" = 1'

DIMENSIONS:

Length	14′ 10″
Width	8′ 7″
Height	10′ 1″

STOWAGE REQUIREMENTS:

Square Feet	127
Cubic Feet	1,287

WEIGHT:

Pounds	35,885

CLAMSHELL BUCKET, F/3/4 Cu. Yd. Shovel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	6' 6"
Width	6' 1"
Height	3'
STOWAGE REQUIREMENTS:	
Square Feet	40
Cubic Feet	120
WEIGHT:	
Pounds	3,000

CRANE BOOM, F/3/4 Cu. Yd. Shovel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	16' 7"
Width	3' 5"
Height	5' 5"
STOWAGE REQUIREMENTS:	
Square Feet	56
Cubic Feet	301
WEIGHT:	
Pounds	2,760

DRAGLINE BUCKET, F/3/4 Cu. Yd. Shovel





DIMENSIONS:	
Length	5' 8"
Width	4' 5"
Height	5' 4"
STOWAGE REQUIREMENTS:	
Square Feet	26
Cubic Feet	136
WEIGHT:	
Pounds	1,900

DIPPER STICK, Boom, Bucket, F/3/4 Cu. Yd. Shovel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20'
Width	3' 2"
Height	5' 8"

STOWAGE REQUIREMENTS:	
Square Feet	64
Cubic Feet	365

WEIGHT:	
Pounds	5,960

PILE DRIVER CONVERSION UNIT, F/3/4 Cu. Yd. Shovel



SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**38' 10"**
Width	**3'**
Height	**2'**
STOWAGE REQUIREMENTS:	
Square Feet	**116**
Cubic Feet	**233**
WEIGHT:	
Pounds	**5,810**

SPRAYER, Paint, Camouflage, Trailer-Mounted





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	5′ 10″
Width	3′ 4″
Height	4′ 6″
STOWAGE REQUIREMENTS:	
Square Feet	19
Cubic Feet	86
WEIGHT:	
Pounds	480

STERILIZATION AND BATH UNIT, Mobile





DIMENSIONS:	
Length	12' 6"
Width	7' 1"
Height	7' 1"
STOWAGE REQUIREMENTS:	
Square Feet	89
Cubic Feet	631
WEIGHT:	
Pounds	6,680

TRAILER, 4-TON, 4-Wheel, Tank, 800 gal.

~~TANK, Service, Asphalt Emulsion, 800 Gal.~~

f/asphalt Emulsion Distributor.





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	14' 7"
Width	7' 1"
Height	7' 2"
STOWAGE REQUIREMENTS:	
Square Feet	104
Cubic Feet	747
WEIGHT:	
Pounds	5,700

TRENCHER, Rotary Wheel





DIMENSIONS:

Length	25′ 5″
Width	8′
Height	10′ 8″

STOWAGE REQUIREMENTS:

Square Feet	203
Cubic Feet	2,172

WEIGHT:

Pounds	12,000

WATER PURIFICATION UNIT, Portable
WATER PURIFICATION FILTER, Portable









SCALE: 1/8" = 1'

	UNIT		FILTER
DIMENSIONS:		**DIMENSIONS**	
Length	2' 10"	**Length**	2' 4"
Width	2' 4"	**Width**	2' 4"
Height	3' 7"	**Height**	4' 1"
STOWAGE REQUIREMENTS:		**STOWAGE REQUIREMENTS:**	
Square Feet	6	**Square Feet**	5
Cubic Feet	23	**Cubic Feet**	22
WEIGHT		**WEIGHT**	
Pounds	422	**Pounds**	537

WELDER, 200 Amp., Gasoline Engine Driven





SCALE: 1/8" - 1'

DIMENSIONS:	
Length	9' 8"
Width	6'
Height	5' 1"
STOWAGE REQUIREMENTS:	
Square Feet	58
Cubic Feet	297
WEIGHT:	
Pounds	2,000

WELDER, 300 Amp., Gasoline Engine Driven (Lincoln)





SCALE 1/8" = 1'

DIMENSIONS:	
Length	10' 1"
Width	6'
Height	6' 8"
STOWAGE REQUIREMENTS:	
Square Feet	60
Cubic Feet	406
WEIGHT:	
Pounds	3,530

WELDER, 300 Amp., Gasoline Engine Driven (P&H)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10′
Width	4′ 5″
Height	5′ 10″
STOWAGE REQUIREMENTS:	
Square Feet	44
Cubic Feet	255
WEIGHT:	
Pounds	2,580

WINCH, Diesel Operated, Complete





DIMENSIONS:	
Length	15'
Width	8' 8"
Height	7' 6"
STOWAGE REQUIREMENTS:	
Square Feet	130
Cubic Feet	999
WEIGHT:	
Pounds	31,360

ORDNANCE
EQUIPMENT

AMPHIBIAN TRACTOR, LVT (2) or (A2)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	26' 1"
Width	10' 8"
Height	8' 1"
STOWAGE REQUIREMENTS:	
Square Feet	278
Cubic Feet	2,246
WEIGHT:	
Pounds	27,600

AMPHIBIAN TRACTOR, LVT (3)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	24' 2"
Width	10' 10"
Height	8' 6"
STOWAGE REQUIREMENTS:	
Square Feet	261
Cubic Feet	2,219
WEIGHT:	
Pounds	28,000

AMPHIBIAN TRACTOR, LVT (4)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**26' 1"**
Width	**10' 8"**
Height	**8' 3"**
STOWAGE REQUIREMENTS:	
Square Feet	**278**
Cubic Feet	**2,294**
WEIGHT:	
Pounds	**25,350**

ARMORED AMPHIBIAN (LVT (A) (4)), W/Armament





SCALE: 1/8" = 1'

DIMENSIONS:

Length	26' 1"
Width	10' 8"
Height	10' 3"

STOWAGE REQUIREMENTS:

Square Feet	278
Cubic Feet	2,850

WEIGHT:

Pounds	38,000

CARRIAGE, Motor, 105MM Howitzer, M7 or M7B1, W/Armament





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**18' 7"**
Width	**9' 6"**
Height	**9' 8"**
STOWAGE REQUIREMENTS:	
Square Feet	**177**
Cubic Feet	**1,705**
WEIGHT:	
Pounds	**52,000**

FINDER, Height, 13-1/2 Feet, M1A1, Complete, W/Cradle





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	15'
Width	2' 6"
Height	2' 4"
STOWAGE REQUIREMENTS:	
Square Feet	38
Cubic Feet	86
WEIGHT:	
Pounds	1,800

GENERATING UNIT, M7, W/Trailer, M7 or M7A1





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	16' 4"
Width	8' 1"
Height	6' 5"
STOWAGE REQUIREMENTS:	
Square Feet	165
Cubic Feet	1,267
WEIGHT:	
Pounds	8,800

GUN, 20MM, Antiaircraft, MK IV





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	8′
Width	4′ 9″
Height	5′ 7″
STOWAGE REQUIREMENTS:	
Square Feet	37
Cubic Feet	207
WEIGHT:	
Pounds	1,695

GUN, 37MM, M3 (Antitank)




5'2"
13'2"
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	13′ 2″
Width	5′ 2″
Height	3′ 4″
STOWAGE REQUIREMENTS:	
Square Feet	69
Cubic Feet	228
WEIGHT:	
Pounds	912

GUN, Automatic, 40MM, M1





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20′ 10″
Width	5′ 10″
Height	7′
STOWAGE REQUIREMENTS:	
Square Feet	114
Cubic Feet	798
WEIGHT:	
Pounds	6,000

GUN, Motor Carriage, 75MM, M3, W/Armament




6'10"
20'4"
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20′ 4″
Width	6′ 10″
Height	8′
STOWAGE REQUIREMENTS:	
Square Feet	139
Cubic Feet	1,110
WEIGHT:	
Pounds	18,400

GUN, 90MM, AA, M1





DIMENSIONS:	
Length	20′ 10″
Width	8′ 5″
Height	9′ 4″
STOWAGE REQUIREMENTS:	
Square Feet	175
Cubic Feet	1,625
WEIGHT:	
Pounds	19,300

Gun, 155MM, M1, or M1A1





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	34′ 4″
Width	8′ 4″
Height	8′ 6″
STOWAGE REQUIREMENTS:	
Square Feet	286
Cubic Feet	2,431
WEIGHT:	
Pounds	29,900

HOWITER, Pack, 75MM, M1A1, W/Carriage





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	9' 5"
Width	4'
Height	4' 4"
STOWAGE REQUIREMENTS:	
Square Feet	38
Cubic Feet	162
WEIGHT:	
Pounds	1,270

HOWITZER, 105MM, M2A1





SCALE: 1/8" = 1'

DIMENSIONS:

Length	20' 10"
Width	7'
Height	6'

STOWAGE REQUIREMENTS:

Square Feet	146
Cubic Feet	875

WEIGHT:

Pounds	4,300

HOWITZER, 155MM, M1





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	22' 2"
Width	7' 10"
Height	6' 6"
STOWAGE REQUIREMENTS:	
Square Feet	174
Cubic Feet	1,146
WEIGHT:	
Pounds	9,164

POWER UNIT, F/Searchlight





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**9'**
Width	**5' 6"**
Height	**6' 2"**
STOWAGE REQUIREMENTS:	
Square Feet	**50**
Cubic Feet	**307**
WEIGHT:	
Pounds	**4,400**

PROJECTOR, Target Rocket, M1





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	13' 4"
Width	5' 7"
Height	3' 9"
STOWAGE REQUIREMENTS:	
Square Feet	74
Cubic Feet	283
WEIGHT:	
Pounds	750

SEARCHLIGHT, AA, 60", Mobile Unit





SCALE: 1/8" = 1'

DIMENSIONS:

Length	8' 4"
Width	8' 2"
Height	7' 4"

STOWAGE REQUIREMENTS:

Square Feet	67
Cubic Feet	491

WEIGHT:

Pounds	4,300

TANK, Medium, M4A2 or M4A3 W/Bulldozer, Tank Mounting





SCALE: 1/8" = 1'

DIMENSIONS:

Length	25′ 9″
Width	12′ 6″
Height	9′ 6″

STOWAGE REQUIREMENTS:

Square Feet	322
Cubic Feet	3,058

WEIGHT:

Pounds	77,200

Change No. 1—4-20-45

TANK, Medium, M4A2 or M4A3, W/75MM Gun





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**20' 8"**
Width	**8' 7"**
Height	**9' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**177**
Cubic Feet	**1,672**
WEIGHT:	
Pounds	**68,400**

TANK, Medium, M4A3, W/105MM Howitzer





SCALE: 1/8" - 1'

DIMENSIONS:	
Length	**20' 8"**
Width	**8' 7"**
Height	**9' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**177**
Cubic Feet	**1,672**
WEIGHT:	
Pounds	**69,600**

VEHICLE, Tank Recovery, M32B2 or M32B3 W/Armament





SCALE: 1/8" = 1'

DIMENSIONS:

Length	19' 5"
Width	8' 11"
Height	9'

STOWAGE REQUIREMENTS:

Square Feet	173
Cubic Feet	1,557

WEIGHT:

Pounds	61,700

TRACTORS

TRACTOR, Light, TD-9 W/Athey Mobile Loader





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20' 5"
Width	7'
Height	10' 11"
STOWAGE REQUIREMENTS:	
Square Feet	143
Cubic Feet	1,560
WEIGHT:	
Pounds	18,200

TRACTOR, MG1 or MG2, Cletrac (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:

Length	13′ 10″
Width	5′ 10″
Height	5′ 8″

STOWAGE REQUIREMENTS:

Square Feet	81
Cubic Feet	456

WEIGHT:

Pounds	14,700

TRACTOR, ~~Medium~~ Light, TD-9





SCALE: 1/8" = 1'

DIMENSIONS:

Length	10' 6"
Width	6' 5"
Height	6' 7"

STOWAGE REQUIREMENTS:

Square Feet	67
Cubic Feet	441

WEIGHT:

Pounds	11,912

Light, TD.9

TRACTOR, ~~Medium,~~ W/Angledozer





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	13' 6"
Width	10' 2"
Height	5' 8"
STOWAGE REQUIREMENTS:	
Square Feet	137
Cubic Feet	788
WEIGHT:	
Pounds	12,135

Light, TD-9

TRACTOR, ~~Medium~~, W/Dozer Shovel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	15′ 10″
Width	6′ 4″
Height	8′ 4″
STOWAGE REQUIREMENTS:	
Square Feet	102
Cubic Feet	852
WEIGHT:	
Pounds	18,480

TRACTOR, Medium, TD-14 W/Power Control Unit





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	11' 7"
Width	7' 8"
Height	7' 8"
STOWAGE REQUIREMENTS:	
Square Feet	89
Cubic Feet	688
WEIGHT:	
Pounds	19,270

Light, TD-9

TRACTOR, ~~Medium,~~ W/TV-9 Crane





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	9' 10"
Width	6' 8"
Height	6' 6"
STOWAGE REQUIREMENTS:	
Square Feet	66
Cubic Feet	427
WEIGHT:	
Pounds	18,000

NOTE: SHIPPED W/BOOM DISMANTLED

TRACTOR, Heavy, TD. 18
W/power Control Unit





SCALE: 1/8" = 1'

DIMENSIONS:

Length	13' 6"
Width	7' 1"
Height	7' 1"

STOWAGE REQUIREMENTS:

Square Feet	97
Cubic Feet	686

WEIGHT:

Pounds	26,750

Medium, TD.14 Armored

TRACTOR, ~~Heavy, Armored~~


USMC
73815
USMC 73815



SCALE: 1/8" = 1'

DIMENSIONS:	
Length	13' 8"
Width	9' 8"
Height	7' 3"
STOWAGE REQUIREMENTS:	
Square Feet	131
Cubic Feet	940
WEIGHT:	
Pounds	27,800

Medium, TD-14

TRACTOR, ~~Heavy,~~ W/Angledozer





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**15' 10"**
Width	**12'**
Height	**7' 9"**
STOWAGE REQUIREMENTS:	
Square Feet	**149**
Cubic Feet	**1,144**
WEIGHT:	
Pounds	**23,580**

Medium, TD-14 W/Angledozer

TRACTOR, ~~Heavy, W/Bullgrader~~





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**20' 6"**
Width	**12' 7"**
Height	**7' 7"**
STOWAGE REQUIREMENTS:	
Square Feet	**258**
Cubic Feet	**1,963**
WEIGHT:	
Pounds	**30,270**

Medium, TD-14

TRACTOR, ~~Heavy,~~ W/Bull Clamshovel





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	16'
Width	9' 10"
Height	7' 6"
STOWAGE REQUIREMENTS·	
Square Feet	156
Cubic Feet	1,192
WEIGHT:	
Pounds	27,300

TRACTOR, Heavy TD-18, W/Front End Winch





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	15' 4"
Width	7' 10"
Height	8'
STOWAGE REQUIREMENTS:	
Square Feet	121
Cubic Feet	946
WEIGHT:	
Pounds	26,990

Medium, TD-14, w/ Hughes-Keenan

TRACTOR, ~~Heavy, W/16Ft. Roustabout Crane~~
~~(360° Traverse)~~

MC-2R Crane.





DIMENSIONS:

Length	22' 5"
Width	7' 9"
Height	9'

STOWAGE REQUIREMENTS:

Square Feet	174
Cubic Feet	1,564

WEIGHT:

Pounds	22,000

TRACTOR, Heavy, TD.18 W/ Heil Crane





102

SCALE: 1/8" = 1'

DIMENSIONS:

Length	32′ 6″
Width	9′
Height	10′ 6″

STOWAGE REQUIREMENTS:

Square Feet	293
Cubic Feet	3,071

WEIGHT:

Pounds	26,120

TRACTOR, Heavy, TD-18 W/Double Drum Power Take-off, ~~TD-18~~





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	14'
Width	7' 11"
Height	7' 4"
STOWAGE REQUIREMENTS:	
Square Feet	111
Cubic Feet	807
WEIGHT:	
Pounds	26,750

TRACTOR, Heavy, TD-18 W/ Power Control Unit





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	14'
Width	7' 10"
Height	7' 4"
STOWAGE REQUIREMENTS:	
Square Feet	110
Cubic Feet	807
WEIGHT:	
Pounds	25,615

TRACTOR, Light Farmall, H W/ Rubber Tires ~~or Metal Wheels~~ General Purpose





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**11' 1"**
Width	**6' 6"**
Height	**6' 4"**
STOWAGE REQUIREMENTS:	
Square Feet	**72**
Cubic Feet	**455**
WEIGHT:	
Pounds	**3,790**

TRACTOR, Wheel, 3-1/2 Ton, 4 x 4 (AVN)
(Minneapolis Moline)





SCALE: 1/8" = 1'

DIMENSIONS:

Length	13' 6"
Width	6'
Height	5'

STOWAGE REQUIREMENTS:

Square Feet	81
Cubic Feet	405

WEIGHT:

Pounds	7,040

TRAILERS

TRAILER, 1/4-Ton, 2-Wheel, Cargo





SCALE: 1/8" - 1'

DIMENSIONS:	
Length	8' 11"
Width	4' 9"
Height	3' 6"
STOWAGE REQUIREMENTS:	
Square Feet	43
Cubic Feet	150
WEIGHT:	
Pounds	550

TRAILER, 1/2-Ton, 2-Wheel, Dump





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**7' 11"**
Width	**4' 10"**
Height	**3' 11"**
STOWAGE REQUIREMENTS:	
Square Feet	**38**
Cubic Feet	**148**
WEIGHT:	
Pounds	**1,908**

TRAILER, 1-Ton, 2-Wheel, Cargo





SCALE: 1/8" = 1'

DIMENSIONS:

Length	11′ 2″
Width	5′ 4″
Height	4′ 6″

STOWAGE REQUIREMENTS:

Square Feet	59
Cubic Feet	267

WEIGHT:

Pounds	1,500

TRAILER, 1-Ton, 2-Wheel, Greasing





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10' 6"
Width	5' 10"
Height	7' 5"
STOWAGE REQUIREMENTS:	
Square Feet	61
Cubic Feet	451
WEIGHT:	
Pounds	3,300

TRAILER, 1-Ton, 2-Wheel, High Pressure Cleaning Unit





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10′ 6″
Width	6′ 9″
Height	6′ 6″
STOWAGE REQUIREMENTS:	
Square Feet	70
Cubic Feet	457
WEIGHT:	
Pounds	1,780

TRAILER, 1-Ton, 2-Wheel, K-52, PE-95
TRAILER, 1-Ton, 2-Wheel, Radio (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**12' 1"**
Width	**6' 2"**
Height	**6' 2"**
STOWAGE REQUIREMENTS:	
Square Feet	**75**
Cubic Feet	**465**
WEIGHT:	
Pounds	**3,280**

TRAILER, 1-Ton, 2-Wheel, Stockroom




7'
13'4"
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**13' 4"**
Width	**7'**
Height	**6' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**93**
Cubic Feet	**596**
WEIGHT:	
Pounds	**4,820**

TRAILER, 1-Ton, 2-Wheel, Water, 300 Gal.





SCALE: 1/8" = 1'

DIMENSIONS:

Length	11' 9"
Width	6' 3"
Height	5' 2"

STOWAGE REQUIREMENTS:

Square Feet	73
Cubic Feet	380

WEIGHT:

Pounds	1,600

TRAILER, 2-Ton, 4-Wheel, AA Searchlight





DIMENSIONS:	
Length	**16' 4"**
Width	**8'**
Height	**4' 8"**
STOWAGE REQUIREMENTS:	
Square Feet	**132**
Cubic Feet	**608**
WEIGHT:	
Pounds	**5,140**

TRAILER, 2-Ton, 4-Wheel, Platform, 12′





DIMENSIONS:	
Length	**16′ 9″**
Width	**7′ 1″**
Height	**3′ 8″**
STOWAGE REQUIREMENTS:	
Square Feet	**120**
Cubic Feet	**442**
WEIGHT:	
Pounds	**3,680**

TRAILER, 2-Ton, 4-Wheel, Platform, 15'





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20' 5"
Width	6' 3"
Height	3' 9"
STOWAGE REQUIREMENTS:	
Square Feet	127
Cubic Feet	468
WEIGHT:	
Pounds	3,600

TRAILER, 2-Ton, 4-Wheel, Power Unit (F/Radar Set SK-1M, SP-1M & Mark 33)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**11' 1"**
Width	**6' 8"**
Height	**5' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**75**
Cubic Feet	**406**
WEIGHT:	
Pounds	**4,000**

TRAILER, 2-Ton, 4-Wheel, Stockroom





SCALE: 1/8" = 1'

DIMENSIONS:

Length (Drawbar Detached)	12′ 5″
Width	7′ 5″
Height	8′ 10″

STOWAGE REQUIREMENTS:

Square Feet (Drawbar Detached)	92
Cubic Feet	817

WEIGHT:

Pounds	12,000

TRAILER, 3-Ton, 4-Wheel, Instrument





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	16' 1"
Width	6'
Height	3' 7"
STOWAGE REQUIREMENTS:	
Square Feet	97
Cubic Feet	348
WEIGHT:	
Pounds	3,600

TRAILER, 3-Ton, 4-Wheel, Photographic Equipment
TRAILER, 3-Ton, 4-Wheel, Reproduction Equipment





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	12' 3"
Width	8' 2"
Height	9' 8"
STOWAGE REQUIREMENTS:	
Square Feet	100
Cubic Feet	957
WEIGHT:	
Pounds (w/photographic equipment)	8,500
Pounds (w/reproduction equipment)	10,500

TRAILER, 3-Ton, 4-Wheel, Water Purification Unit





Scale-1/8"=1'

DIMENSIONS:

Length	13' 4"
Width	7' 5"
Height	8' 4"

STOWAGE REQUIREMENTS:

Square Feet	98
Cubic Feet	817

WEIGHT:

Pounds	9,110

TRAILER, 3-Ton, Cargo, Track-Laying





DIMENSIONS:	
Length	**16' 2"**
Width	**7' 2"**
Height	**4' 5"**
STOWAGE REQUIREMENTS:	
Square Feet	**116**
Cubic Feet	**512**
WEIGHT:	
Pounds	**6,770**

TRAILER, 3-~~1/2~~-Ton, 2-Wheel, Cargo ~~Carrier, Watertight~~ Amphibian.

TRAILER, 2 Wheel, Medical Amphibian





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20' 9"
Width	7' 10"
Height	6'
STOWAGE REQUIREMENTS:	
Square Feet	162
Cubic Feet	975
WEIGHT:	
Pounds	~~3,960~~ 12,000

TRAILER, 5-Ton, 4-Wheel, Machine Shop No. 1




8'4"
4'1"
15'2"
19'3"
SCALE: 1/8" = 1'

DIMENSIONS:	
Length (Drawbar Detached)	15′ 2″
Width	8′ 4″
Height	9′ 1″
STOWAGE REQUIREMENTS:	
Square Feet (Drawbar Detached)	126
Cubic Feet	1,144
WEIGHT:	
Pounds	11,935

TRAILER, 5-Ton, 4-Wheel, Machine Shop No. 2




7' 11"
19' 10"
16' 3" APPROX.
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	19′ 10″
Width	7′ 11″
Height	9′ 5″
STOWAGE REQUIREMENTS:	
Square Feet	156
Cubic Feet	1,470
WEIGHT:	
Pounds	18,500

TRAILER, 5-Ton, 4-Wheel, Ponton Balk, W/Bolster





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**15' 7"**
Width	**7' 6"**
Height	**4' 2"**
STOWAGE REQUIREMENTS:	
Square Feet	**117**
Cubic Feet	**491**
WEIGHT:	
Pounds	**6,400**

TRAILER, 5-Ton, 4-Wheel, Ponton Balk, W/O Bolster





SCALE: 1/8" - 1'

DIMENSIONS:	
Length	15′ 7″
Width	7′ 5″
Height	4′ 2″
STOWAGE REQUIREMENTS:	
Square Feet	117
Cubic Feet	491
WEIGHT:	
Pounds	6,150

TRAILER, Pole, 2-Wheel, Ponton Balk





DIMENSIONS:	
Length	15′ 2″
Width	7′ 2″
Height	5′ 7″
STOWAGE REQUIREMENTS:	
Square Feet	109
Cubic Feet	613
WEIGHT:	
Pounds	3,300

TRAILER, 5-Ton, 4-Wheel, SKD-2226
(Radio Intelligence)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	18' 4"
Width	8'
Height	10' 6"
STOWAGE REQUIREMENTS:	
Square Feet	146
Cubic Feet	1,537
WEIGHT:	
Pounds	16,951

TRAILER, 6-Ton, Cargo, Track-laying





SCALE: 1/8" = 1'

DIMENSIONS:

Length	18′ 4″
Width	8′
Height	4′
Height (W/Stakes up)	6′ 1″

STOWAGE REQUIREMENTS:

Square Feet	147
Cubic Feet	587
Cubic Feet (W/Stakes up)	892

WEIGHT:

Pounds	9,712

TRAILER, 6-Ton, 26', Semi-Stake, W/Detachable Front Bogie





SCALE: 1/8" = 1'

DIMENSIONS:

Length	26' 4"
Width	8'
Height (Stakes Up)	6' 1"
Height (Stakes Folded)	4' 6"

STOWAGE REQUIREMENTS:

Square Feet	211
Cubic Feet (Stakes Folded)	950

WEIGHT:

Pounds	6,275

TRAILER, 7-Ton, 6-Wheel (Operating)
(F/Radar Set SP-1M)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20′
Width	8′
Height	10′ 3″
STOWAGE REQUIREMENTS:	
Square Feet	160
Cubic Feet	1,640
WEIGHT:	
Pounds	14,000

NOTE: Measurements made with drawbar detached.

TRAILER, 7-Ton, 6-Wheel (Equipment)

(F/RADAR SET SP-1M)





SCALE: 1/8" = 1'

DIMENSIONS:

Length	20'
Width	8'
Height	10' 3"

STOWAGE REQUIREMENTS:

Square Feet	160
Cubic Feet	1,640

WEIGHT:

Pounds	15,000

NOTE: Measurements made with drawbar detached.

TRAILER, 7-Ton, 4-Wheel, Power

(F/Radio Set SCR-270-B (NAVY))
(F/Radio Set SCR-270-D (NAVY))





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	18' 4"
Width	8'
Height	10' 6"
STOWAGE REQUIREMENTS:	
Square Feet	146
Cubic Feet	1,537
WEIGHT:	
Pounds	14,000

NOTE: Measurements made with drawbar detached.

TRAILER, 8-Ton, 6-Wheel (Operating)

(F/Radar Set SK-1M)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**20'**
Width	**8'**
Height	**10' 3"**
STOWAGE REQUIREMENTS:	
Square Feet	**160**
Cubic Feet	**1,640**
WEIGHT:	
Pounds	**15,000**

TRAILER, ~~10~~ 6-Ton, Semi-Trailer, 2-Wheel, Van Type, Laundry





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	22′ 8″
Width	8′ 2″
Height	10′ 11″
STOWAGE REQUIREMENTS:	
Square Feet	183
Cubic Feet	1,995
WEIGHT:	
Pounds	10,650

TRAILER, 11-Ton, 4-Wheel (Operating)

(F/Radio Set SCR-270-B (NAVY))
(F/Radio Set SCR-270-D (NAVY))





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	18' 4"
Width	8'
Height	10' 6"
STOWAGE REQUIREMENTS:	
Square Feet	146
Cubic Feet	1,537
WEIGHT:	
Pounds	21,600

NOTE: Measurements made with drawbar detached.

TRAILER, 13-Ton, 4-Wheel (Antenna)

(F/Radio Set SCR-270-B (NAVY))
(F/Radio Set SCR-270-D (NAVY))





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**30′**
Width	**7′ 6″**
Height	**12′**
STOWAGE REQUIREMENTS:	
Square Feet	**225**
Cubic Feet	**2,700**
WEIGHT:	
Pounds	**24,700**

TRAILER, 15-18-Ton, Machinery





DIMENSIONS:	
Length	24' 6"
Width	8' 1"
Height	3' 6"
STOWAGE REQUIREMENTS:	
Square Feet	198
Cubic Feet	695
WEIGHT:	
Pounds	8,500

TRAILER, 16-Ton, 4-Wheel, Low Bed





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	29′
Width	8′
Height	4′ 9″
STOWAGE REQUIREMENTS:	
Square Feet	232
Cubic Feet	1,090
WEIGHT:	
Pounds	8,500

TRAILER, 20-Ton, Drop Frame (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**39' 10"**
Width	**8'**
Height	**5' 3"**
STOWAGE REQUIREMENTS:	
Square Feet	**319**
Cubic Feet	**1,673**
WEIGHT:	
Pounds	**12,780**

TRAILER, 25-Ton, Low Bed Semi-Trailer





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	36′ 9″
Width	10′
Height	5′ 3″
STOWAGE REQUIREMENTS:	
Square Feet	368
Cubic Feet	1,930
WEIGHT:	
Pounds	15,000

TRAILER, 45-Ton, 12-Wheel, M9





SCALE: 1/8" = 1'

DIMENSIONS:

Length (w/drawbar)	29′ 8″
Length (w/o drawbar)	23′
Width	9′ 6″
Height	4′ 9″

STOWAGE REQUIREMENTS:

Square Feet (w/drawbar)	282
Square Feet (w/o drawbar)	219
Cubic Feet (w/drawbar)	1,313
Cubic Feet (w/o drawbar)	1,038

WEIGHT:

Pounds	22,020

TRAILER, Bomb, Mark I (AVN)




13' 0" APPROX.
16' 2"
5' 5"

SCALE: 1/8" = 1'

DIMENSIONS:	
Length	16' 2"
Width	5' 5"
Height	2' 11"
STOWAGE REQUIREMENTS:	
Square Feet	88
Cubic Feet	254
WEIGHT:	
Pounds	1,440

TRAILER, Bomb, Mark II (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**9' 2"**
Width	**3' 8"**
Height	**1' 10"**
STOWAGE REQUIREMENTS:	
Square Feet	**33**
Cubic Feet	**59**
WEIGHT:	
Pounds	**410**

TRAILER, Bomb, Mark V (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**17' 3"**
Width	**7' 9"**
Height	**3' 11"**
STOWAGE REQUIREMENTS:	
Square Feet	**132**
Cubic Feet	**517**
WEIGHT:	
Pounds	**1,440**

TRAILER, Cable Splicer, ~~Telephone, 1/4-Ton,~~ K-38





SCALE: 1/8" - 1'

DIMENSIONS:	
Length	6' 8"
Width	4' 9"
Height	4'
STOWAGE REQUIREMENTS:	
Square Feet	31
Cubic Feet	124
WEIGHT:	
Pounds	660

TRAILER, Camp Lighting, 110 AC, 10 KVA (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:

Length	8' 9"
Width	5' 4"
Height	5' 8"

STOWAGE REQUIREMENTS:

Square Feet	46
Cubic Feet	258

WEIGHT:

Pounds	2,520

TRAILER, Chrysler, Fire Fighting





DIMENSIONS:	
Length	**9' 5"**
Width	**5' 11"**
Height	**6'**
STOWAGE REQUIREMENTS:	
Square Feet	**56**
Cubic Feet	**333**
WEIGHT:	
Pounds	**3,360**

TRAILER, Combination Cable Reel and Pole, K-37





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	11′ 9″
Width	5′ 6″
Height	7′ 9″
STOWAGE REQUIREMENTS:	
Square Feet	65
Cubic Feet	501
WEIGHT:	
Pounds	2,700

TRAILER, Fire & Decontamination (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10' 6"
Width	5' 4"
Height	6' 3"
STOWAGE REQUIREMENTS:	
Square Feet	56
Cubic Feet	350
WEIGHT:	
Pounds	2,500

TRAILER, Dolly, Converter, F/Trailer, Gasoline, 3200 Gal. (AVN)





DIMENSIONS:	
Length	11' 3"
Width	7' 9"
Height	4' 3"
STOWAGE REQUIREMENTS:	
Square Feet	86
Cubic Feet	362
WEIGHT:	
Pounds	2,500

TRAILER, Gasoline, 2000 Gal. Capacity (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	24′ 2″
Width	8′
Height	8′ 8″
STOWAGE REQUIREMENTS:	
Square Feet	193
Cubic Feet	1,658
WEIGHT:	
Pounds	11,500

TRAILER, Gasoline, 3200 Gal. Capacity, W/Dolly (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	31' 6"
Width	8' 2"
Height	8' 11"
STOWAGE REQUIREMENTS:	
Square Feet	255
Cubic Feet	2,271
WEIGHT:	
Pounds (W/Dolly)	14,480
Pounds (W/O Dolly)	11,980

TRAILER, Mobile Hospital Operating Room


U.S. MARINE CORPS
105751



SCALE: 1/8" = 1'

DIMENSIONS:

Length	19' 10"
Width	7' 11"
Height	9' 11"

STOWAGE REQUIREMENTS:

Square Feet	157
Cubic Feet	1,556

WEIGHT:

Pounds	11,000

TRAILER, Oil Refiner





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**15' 5"**
Width	**7' 11"**
Height	**9' 6"**
STOWAGE REQUIREMENTS:	
Square Feet	**122**
Cubic Feet	**1,160**
WEIGHT:	
Pounds	**18,750**

TRAILER, Photographic (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	22′ 2″
Width	7′ 4″
Height	8′ 8″
STOWAGE REQUIREMENTS:	
Square Feet	161
Cubic Feet	1,387
WEIGHT:	
Pounds	6,740

TRAILER, Pole Hauling ~~& Cargo,~~ K-36





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10' 3"
Width	7'
Height	5' 9"
STOWAGE REQUIREMENTS:	
Square Feet	72
Cubic Feet	413
WEIGHT:	
Pounds	2,067

TRAILER, Power, F/Radio & Radar Repair Truck





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	9′ 6″
Width	5′ 8″
Height	4′ 3″
STOWAGE REQUIREMENTS:	
Square Feet	54
Cubic Feet	229
WEIGHT:	
Pounds	3,075

TRAILER, 2-Wheel, Shower Unit, 24 Head





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**11' 8"**
Width	**6'**
Height	**5'**
STOWAGE REQUIREMENTS:	
Square Feet	**70**
Cubic Feet	**351**
WEIGHT:	
Pounds	**4,350**

TRAILER, 1-Ton, 2-Wheel, Steam Jenny,

(Kerrick Kleaner) (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	6' 4"
Width	5' 10"
Height	5'
STOWAGE REQUIREMENTS:	
Square Feet	37
Cubic Feet	183
WEIGHT:	
Pounds	1,740

TRUCKS

TRUCKS

AMBULANCE, 1/4-Ton, 4 x 4




5' 2"
10' 10"
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	10′ 10″
Width	5′ 2″
Height	5′ 11″
STOWAGE REQUIREMENTS:	
Square Feet	56
Cubic Feet	331
WEIGHT:	
Pounds	2,300

AMBULANCE, 1/2-Ton, 4 x 4




6' 5"
16'
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**16'**
Width	**6' 5"**
Height	**5' 11"**
STOWAGE REQUIREMENTS:	
Square Feet	**104**
Cubic Feet	**614**
WEIGHT:	
Pounds	**4,950**

CAR, 5-Passenger (Chevrolet)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**15′ 8″**
Width	**6′ 2″**
Height	**5′ 11″**
STOWAGE REQUIREMENTS:	
Square Feet	**97**
Cubic Feet	**574**
WEIGHT:	
Pounds	**3,210**

CARRIER, Personnel, Half-Track, M-3, Radio-Equipped





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**20' 4"**
Width	**6' 10"**
Height	**8'**
STOWAGE REQUIREMENTS:	
Square Feet	**139**
Cubic Feet	**1,110**
WEIGHT:	
Pounds	**17,650**

Station Wagon

~~CARRYALL, 8 Passenger,~~ 4 x 4





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	15' 6"
Width	6' 6"
Height	6' 10"
STOWAGE REQUIREMENTS:	
Square Feet	101
Cubic Feet	685
WEIGHT:	
Pounds	5,750

STATION WAGON, 4 x ~~4~~ 2




6'4"
16' 6"
SCALE: 1/8" = 1'

DIMENSIONS:

Length	16' 6"
Width	6' 4"
Height	6' 4"

STOWAGE REQUIREMENTS:

Square Feet	104
Cubic Feet	655

WEIGHT:

Pounds	3,600

TRUCK, 1/4-Ton, 4 x 4




5' 1"
10' 11"
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**10′ 11″**
Width	**5′ 1″**
Height	**4′ 6″**
STOWAGE REQUIREMENTS:	
Square Feet	**56**
Cubic Feet	**250**
WEIGHT:	
Pounds	**2,450**

TRUCK, 1/2-Ton, 4 x 2, Pickup ~~(Base Depot)~~





DIMENSIONS:	
Length	16' 5"
Width	6'
Height	6' 2"
STOWAGE REQUIREMENTS:	
Square Feet	98
Cubic Feet	610
WEIGHT:	
Pounds	2,960

TRUCK, 3/4-Ton, 4 x 4, Weapons Carrier





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	13' 8"
Width	6' 11"
Height	5' 2"
STOWAGE REQUIREMENTS:	
Square Feet	95
Cubic Feet	492
WEIGHT:	
Pounds	5,550

TRUCK, 1-Ton, 4 x 4, Cargo

TRUCK, 1-Ton, 4 x 4, Light Repair

TRUCK, 1-Ton, 4 x 4, Reconnaissance





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	17' 5"
Width	6' 11"
Height	5' 9"
STOWAGE REQUIREMENTS:	
Square Feet	120
Cubic Feet	696
WEIGHT:	
Pounds	5,772

TRUCK, 1-Ton, Greasing





SCALE: 1/8" = 1'

DIMENSIONS:

Length	21' 5"
Width	7' 6"
Height	11' 8"

STOWAGE REQUIREMENTS:

Square Feet	161
Cubic Feet	1,878

WEIGHT:

Pounds	8,850

TRUCK, 1-1/2-Ton, Cargo (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**18′ 6″**
Width	**7′ 2″**
Height	**7′ 4″**
STOWAGE REQUIREMENTS:	
Square Feet	**133**
Cubic Feet	**972**
WEIGHT:	
Pounds	**8,040**

TRUCK, 1-1/2-Ton, 4 x 2, Fire, 500 Gal.





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	22' 8"
Width	7' 5"
Height	7' 9"
STOWAGE REQUIREMENTS:	
Square Feet	167
Cubic Feet	1,288
WEIGHT:	
Pounds	7,830

TRUCK, 1-1/2-Ton, 4 x 4, K-51 (F/SCR-299)
TRUCK, 1-1/2-Ton, 4 x 4, Radio (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	18' 5"
Width	8' 1"
Height	8' 7"
STOWAGE REQUIREMENTS:	
Square Feet	149
Cubic Feet	1,281
WEIGHT:	
Pounds	9,760

TRUCK, 1-1/2-Ton, 6 x 6, Cargo (Dodge)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**18' 9"**
Width	**6' 11"**
Height	**4' 8"**
STOWAGE REQUIREMENTS:	
Square Feet	**130**
Cubic Feet	**607**
WEIGHT:	
Pounds	**7,000**

TRUCK, 2-1/2-Ton, 4 x 4, Cargo (Prime Mover)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**18′ 5″**
Width	**7′ 7″**
Height	**8′ 8″**
STOWAGE REQUIREMENTS:	
Square Feet	**140**
Cubic Feet	**1,209**
WEIGHT:	
Pounds	**14,500**

TRUCK 2-1/2-Ton, 6 x 6, Amphibian





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**31′**
Width	**8′**
Height	**7′ 1″**
STOWAGE REQUIREMENTS:	
Square Feet	**248**
Cubic Feet	**1,761**
WEIGHT:	
Pounds	**14,880**

(1

(4

TRUCK, 2-1/2-Ton, 6 x 6,

Artillery Repair, M9A1 W/Load or
Automobile Repair, M8A1 W/Load A or
Electric Repair, M12A1, W/Load or
Instrument Bench, M23A1, W/Load or
Instrument Repair, M10A1, W/Load A or
Machine Shop, M16A1 W/Load A or
Small Arms Repair, M7A1, W/Load A or
W/Ordnance Maintenance Set "F" (Artillery Repair) or
Welding, W/Maintenance Load L (Welding Truck)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**19'**
Width	**7' 9"**
Height	**9'**
STOWAGE REQUIREMENTS:	
Square Feet	**147**
Cubic Feet	**1,325**
WEIGHT:	
Pounds	**16,807**

NOTE: Weight may vary 500 pounds depending on load.

TRUCK, 2-1/2-Ton, 6 x 6, Cargo





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	23'
Width	7' 10"
Height	6' 6"
STOWAGE REQUIREMENTS:	
Square Feet	179
Cubic Feet	1,166
WEIGHT:	
Pounds	13,666

TRUCK, 2-1/2 Ton, 6 x 6, Dump





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	21'
Width	7' 10"
Height	7' 2"
STOWAGE REQUIREMENTS:	
Square Feet	164
Cubic Feet	1,181
WEIGHT:	
Pounds	13,400

TRUCK, 2-1/2-Ton, 6 x 6, Photographic Repair





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	21' 6"
Width	8'
Height	9' 10"
STOWAGE REQUIREMENTS:	
Square Feet	172
Cubic Feet	1,686
WEIGHT:	
Pounds	15,100

TRUCK, 2-1/2-Ton, 6 x 6, Radio & Radar Repair (AVN)

(Signal Repair, M30)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	22' 9"
Width	7' 10"
Height	10' 2"
STOWAGE REQUIREMENTS:	
Square Feet	178
Cubic Feet	1,812
WEIGHT:	
Pounds	12,058

TRUCK, 2-1/2-Ton, 6 x 6, Stake





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	23'
Width	7' 10"
Height	8'
STOWAGE REQUIREMENTS:	
Square Feet	180
Cubic Feet	1,441
WEIGHT:	
Pounds	13,025

TRUCK, 2-1/2-Ton, 6 x 6, Tank, Gasoline, 750 Gal.





SCALE: 1/8" = 1'

DIMENSIONS:

Length	22′
Width	7′ 8″
Height	7′ 10″

STOWAGE REQUIREMENTS:

Square Feet	169
Cubic Feet	1,320

WEIGHT:

Pounds	12,660

TRUCK, 2-1/2-Ton, 6 x 6, Telephone Construction & Maintenance





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	23′
Width	7′ 10″
Height	8′
STOWAGE REQUIREMENTS:	
Square Feet	180
Cubic Feet	1,441
WEIGHT:	
Pounds	18,525

TRUCK, Tractor, 4 x 2, ~~K 10~~





DIMENSIONS:

Length	20′ 5″
Width	8′
Height	7′ 5″

STOWAGE REQUIREMENTS:

Square Feet	163
Cubic Feet	1,206

WEIGHT:

Pounds	8,340

TRUCK, Tractor, 2-1/2-Ton, 6 x 6





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20′ 8″
Width	7′ 8″
Height	7′ 8″
STOWAGE REQUIREMENTS:	
Square Feet	157
Cubic Feet	1,190
WEIGHT:	
Pounds	13,000

TRUCK, 2-1/2-Ton, 6 x 6, Wrecking





SCALE: 1/8 = 1'

DIMENSIONS:	
Length	**24'**
Width	**7' 7"**
Height	**9' 11"**
STOWAGE REQUIREMENTS:	
Square Feet	**182**
Cubic Feet	**1,806**
WEIGHT:	
Pounds	**16,000**

TRUCK, 3-Ton, 6 x 6, Dump (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:

Length	20'
Width	7' 8"
Height	7' 10"

STOWAGE REQUIREMENTS:

Square Feet	154
Cubic Feet	1,201

WEIGHT:

Pounds	15,000

TRUCK, 12-Ton, Low Bed, Stake Body


USMC
DOSF
USMC



SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**23′ 2″**
Width	**8′ 5″**
Height	**8′ 10″**
STOWAGE REQUIREMENTS:	
Square Feet	**194**
Cubic Feet	**1,708**
WEIGHT:	
Pounds	**11,420**

TRUCK, 12-Ton, 6 x 4, M20





SCALE: 1/8" = 1'

DIMENSIONS:

Length	23′ 4″
Width	8′ 6″
Height	8′ 5″

STOWAGE REQUIREMENTS:

Square Feet	198
Cubic Feet	1,670

WEIGHT:

Pounds	26,650

TRUCK, 4 x 4, Bomb Service, Mark 2 (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	20' 5"
Width	6' 11"
Height	8' 4"
STOWAGE REQUIREMENTS:	
Square Feet	141
Cubic Feet	1,169
WEIGHT:	
Pounds	8,500

TRUCK, 4 x 4, Gasoline, 600 Gal. (International) (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	19' 6"
Width	7' 7"
Height	7' 10"
STOWAGE REQUIREMENTS:	
Square Feet	148
Cubic Feet	1,156
WEIGHT:	
Pounds	10,600

TRUCK, Fire and Rescue (International) (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**19' 3"**
Width	**7' 6"**
Height	**7' 7"**
STOWAGE REQUIREMENTS:	
Square Feet	**145**
Cubic Feet	**1,094**
WEIGHT:	
Pounds	**9,775**

TRUCK-TRACTOR, W/Crane (Autocar) (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**25' 10"**
Width	**8' 2"**
Height	**10' 6"**
STOWAGE REQUIREMENTS:	
Square Feet	**212**
Cubic Feet	**2,222**
WEIGHT:	
Pounds	**23,200**

TRUCK-TRACTOR, W/Crane (Oshkosh) (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	28′
Width	8′ 1″
Height	10′ 7″
STOWAGE REQUIREMENTS:	
Square Feet	227
Cubic Feet	2,404
WEIGHT:	
Pounds	21,000

MISCELLANEOUS

MISCELLANEOUS

APPARATUS, Decontaminating, Power Driven, M4




4'-0"
13'-6"
SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**13′ 6″**
Width	**4′**
Height	**5′ 2″**
STOWAGE REQUIREMENTS:	
Square Feet	**54**
Cubic Feet	**279**
WEIGHT:	
Pounds	**4,666**

CABINET, Fumigation, Methyl Bromide





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	8' 10"
Width	6'
Height	6' 3"
STOWAGE REQUIREMENTS:	
Square Feet	53
Cubic Feet	331
WEIGHT:	
Pounds	1,930

CARGO CARRIER, M29-C, Amphibious





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**15′ 2″**
Width	**5′ 9″**
Height	**5′**
STOWAGE REQUIREMENTS:	
Square Feet	**83**
Cubic Feet	**415**
WEIGHT:	
Pounds	**4,771**

Change No. 1—4-20-45

CRANE, 10-Ton, Truck Mounted





SCALE: 1/8" = 1'

DIMENSIONS:	
Length	**34' 8"**
Width	**8'**
Height	**10' 10"**
STOWAGE REQUIREMENTS:	
Square Feet	**277**
Cubic Feet	**2,990**
WEIGHT:	
Pounds	**30,000**

PALLET,

AA-Hull Repair Shop
BA-Machine Shop
AB-Retriever
BC-LVT Spare Parts
BB-Eng. & Trans. Repair Shop
DA-Consumables



SCALE: 1/8" = 1'

DIMENSIONS:

Length	11' 11"
Width	5' 11"
Height	7' 5"

STOWAGE REQUIREMENTS:

Square Feet	71
Cubic Feet	524

WEIGHT:

Pounds—

AA-Hull Repair Shop	7,500
BA-Machine Shop	7,500
BC-LVT Spare Parts	4,320
AB-Retriever	8,000
BB-Eng. & Trans. Repair Shop	7,000
DA-Consumables	9,500

REPAIR UNIT, 4-Ton, 4-Wheel, Shoe & Textile, 2000 Men (Trailer Mounted)





SCALE: 1/8" = 1'

DIMENSIONS:	
Length (W/O Drawbar)	**18' 6"**
Width	**8' 2"**
Height	**9' 3"**
STOWAGE REQUIREMENTS:	
Square Feet	**150**
Cubic Feet	**1,379**
WEIGHT:	
Pounds	**11,480**

TRUCK, 4000 Lb., Fork (Plane Loader) (AVN)





SCALE: 1/8" = 1'

DIMENSIONS:

Length	9' 9"
Width	6' 6"
Height	9'

STOWAGE REQUIREMENTS:

Square Feet	63
Cubic Feet	570

WEIGHT:

Pounds	6,641

NOTE: When forks are lowered the shorter length of 6' 3" should be considered when computing deck area.

MCPB 124749 1-25-45 2M.

TRUCK, 6000 Lb., Fork Lift, Warehousing



SCALE: 1/8" = 1'

DIMENSIONS:	
Length (w/o fingers)	6' 6"
Width	3' 3"
Height	8'
STOWAGE REQUIREMENTS:	
Square Feet	21
Cubic Feet	167
WEIGHT:	
Pounds	6,270

ORGANIZATION TONNAGE CHART

1 August, 1945

Following tonnage data is presented for general information and as a ready reference guide in making preliminary estimates of shipping requirements. It should not necessarily be construed as a basis for desirable or maximum combat loads. Exact tonnage requirements for each operation must, therefore, still be computed from actual weights and measurements of material to be embarked.

The number of personnel, tonnage of equipment, and fuel estimates herein are based on empirical data for an assault on a large island with a fairly extensive road net.

CLASS V - One CinCPOA unit of fire (13 Dec. 1944) for the unit's T/A allowance of weapons, as of 26 February 1945.

MEAS. TONS = Conversion factor **X** short tons.

CONVERSION FACTORS:					
	Class I	- 1.30;		Class II & IV	- 3.50;
	Class III	- 1.50;		Class **V**	- .81;

Average - 2.6

MCPB 126934 8-11-45 2M

ORGANIZATION TONNAGE CHART

1 August, 1945

Following tonnage data is presented for general information and as a ready reference guide in making preliminary estimates of shipping requirements. It should not necessarily be construed as a basis for desirable or maximum combat loads. Exact tonnage requirements for each operation must, therefore, still be computed from actual weights and measurements of material to be embarked.

The number of personnel, tonnage of equipment, and fuel estimates herein are based on empirical data for an assault on a large island with a fairly extensive road net.

NOTES: Basis of tonnage data:

PERSONNEL - Number embarked by an actual unit typical of the one indicated. Weight of individual, 224 lbs. (1/10 LT), is not included in indicated tonnage.

CLASS I - One day's B ration (6 lbs) for indicated personnel. For weight of one day's supply of other type rations multiply by following percentages:
C - 83.8%; K - 52.8%; D - 17.4%; 10-1 - 75.0%.

CLASS II & IV Material embarked by a unit typical of the one indicated. Initial allowance plus 30 days maintenance was generally the maximum limit on material embarked for the operation concerned.

Square feet tabulated in "Allow" column is that of initial equipment allowances for division, corps and force units as of 23 July 1945.

Square feet tabulated in "Embark" column is that of equipment actually embarked. No broken stowage allowance is included.

CLASS III - Approximate maximum fuel requirements for a day's operation of the vehicles and equipment embarked by the typical unit. See Volume II, Table of Allowances, Table of Fuel Consumption, for estimated hourly fuel requirements per vehicle. Hours of operation per day employed in calculation are as follows: 1/4-ton vehicles - 5; tractors, tracked land, and amphibious vehicles - 12; other vehicles - 8; other equipment - 10. Actual average fuel consumption for a thirty-day period for an Amphibious Corps, including all normally attached units, expressed in gallons per man per day, have been demonstrated to be: Motor Gas - .60; White Gas - .10; Diesel -.24; Kerosene - .01; Lubrication oils - .05; Gear Lubricants - .034 lbs; Grease - .022 lbs.

CLASS V - One CinCPOA unit of fire (13 Dec. 1944) for the unit's T/A allowance of weapons, as of 26 February 1945.

MEAS. TONS = Conversion factor X short tons.

CONVERSION FACTORS: Class I - 1.30; Class II & IV - 3.50;
Class III - 1.50; Class V - .81;
Average - 2.6

MCPB 126934 8-11-45 2M

UNITS		PERSONNEL			CARGO - SHORT TONS (FOR MEASURED TONS - SEE CONVERSION FACTORS IN NOTES)					
FORCE UNITS (CONTINUED)		OFFICER	ENLISTED	TOTAL	I	II & IV	SQ.FT. - VEH., GUNS. ETC. ALLOW	SQ.FT. - VEH., GUNS. ETC. EMBARK	III	V
TRUCK/CO, MT/BN		4	78	82	.2	149.6	7391	4297	1.9	1.6
AUTO/REP/CO, MT/BN		13	241	254	.8	165.7	5338	3754	1.2	1.5
H&S/CO, MT/BN		6	54	60	.2	89.4	1611	843	.6	.2
MT/BN		35	607	642	1.8	853.5	36513	21785	9.4	8.1
VMO		8	29	37	.1	58.1	ND	730	2.5	.2*
RAD/INTELL/PLAT		1	44	45	.1	106.1	829	1115	.5	.1
ROCKET/DET:(PROV)		2	56	58	.2	49.6	2415	2318	1.0	45.0*
OTHER SERVICES										
COMM/UNIT	NAVY	23	151	174	.5	136.4	ND	2665	2.0	0.0
CONST/BN	NAVY	23	860	883	2.6	1375.0	ND	21111	13.3	4.5*
SPECIAL/CONST/BN	NAVY	27	1411	1438	4.3	669.7	ND	3182	3.0	3.6*
MP/CO	ARMY	5	114	149	.4	18.6	ND	514	.2	.1*
AMPHN/TRUCK/CO	ARMY	7	162	169	.5	400.7	ND	13444	14.8	1.5*

SEE NOTES BEFORE USING CHART

*NOT BASED ON T/A ALLOWANCE OF WEAPONS, BUT ON AMOUNTS EMBARKED.

ND - NO DATA AVAILABLE

UNITS	PERSONNEL			CARGO - SHORT TONS (FOR MEASURED TONS - SEE CONVERSION FACTORS IN NOTES)					
FORCE UNITS (CONTINUED)	OFFICER	ENLISTED	TOTAL	I	II & IV	SQ.FT. - VEH., GUNS. ETC.		III	V
						ALLOW	EMBARK		
90MM/BTY, H/AA/GRP	5	91	96	.3	123.3	2027	2094	.8	18.3
GRP/HQ, H/AA/GRP	7	35	42	.1	66.2	2258	1201	.4	.3
HEAVY AA/GRP	27	399	426	1.3	559.4	10366	9577	3.6	73.5
S/L/BTY, AAA/BN	5	135	140	.4	272.1	8514	8181	3.1	1.9
H&S/BTY, AAA/BN	31	181	212	.6	474.	5484	4783	1.8	1.2
AAA/BN	78	937	1015	3.0	1493.8	29695	26703	10.1	91.5
HQ/BTY, AAA/GRP	14	165	179	.5	373.3	2377	8521	1.6	.4*
40MM/BTY, L/AA/GRP	3	117	120	.4	114.66	2810	2488	.9	8.0
GRP/HQ, L/AAA/GRP	3	40	43	.1	36.6	629	765	.3	.1
L/AAA/GRP, DEF/BN	9	274	283	.9	265.92	6249	5741	2.1	16.1
90MM/BTY, H/AAA/GRP	4	117	121	.4	152.02	1868	2126	.8	18.3
GRP/HQ, H/AAA/GRP	4	41	45	.1	68.65	2000	1177	.4	.3
H/AAA/GRP, DEF/BN	20	509	529	1.7	676.73	9472	9681	3.6	73.5
S/L/BTY, DEF/BN	4	172	176	.5	332.4	8458	8325	3.2	1.9
H&S/BTY, DEF/BN	24	253	277	.8	646.33	5770	5042	1.9	4.6
DEF/BN	57	1208	1265	3.9	1921.38	29949	28789	10.8	96.1
CORPS/EVAC/HOSP	27	223	250	.8	329.8	5712	5139	1.4	0.0
AMPHN/TRAC/CO	6	133	139	.4	411.5	9901	8984	15.8	5.7
H&S/CO, AMPHN/TRAC/BN	11	95	106	.3	204.1	5341	3877	6.6	1.7
AMPHN/TRAC/BN	29	494	523	1.5	1438.6	35044	30829	54.0	18.8
ARM/AMPHN/CO	5	141	146	.4	250.9	6544	5798	9.6	39.2
H&S/CO, ARM/AMPHN/BN	14	109	123	.4	154.0	4201	3954	6.5	8.9
ARM/AMPHN/BN	34	673	707	2.0	1157.6	30377	27146	44.9	165.7
AMPHN/TRUCK/CO	6	181	187	.6	386.8	13551	13015	16.6	.9
AMPHN/TRAC/GRP/HQ									
MP/CO, MP/BN	6	100	106	.3	16.5	267	477	.2	.3
HQ/CO, MP/BN	7	37	44	.1	25.1	1052	1247	.5	.1
MP/BN	31	437	468	1.3	91.1	2120	3155	1.3	1.3
155MM/BTY	6	160	166	.5	229.1	4073	3035	2.2	0.0
H&S/BTY, 155MM/GUN/BN	16	145	161	.5	128.6	3703	2481	1.8	1.1
155MM/GUN/BN	34	625	659	2.0	815.9	15922	11586	8.4	150.8
E/CO, SEP/E/BN	6	192	198	.6	253.0	7708	4861	2.8	3.5
H&S/CO, SEP/E/BN	22	255	277	.8	1063.3	10547	9357	5.3	4.5
SEP/E/BN	40	831	871	2.6	1822.3	33671	23940	13.7	15.0
TRUCK/CO, MT/BN	4	78	82	.2	149.6	7391	4297	1.9	1.6
AUTO/REP/CO, MT/BN	13	241	254	.8	165.7	5338	3754	1.2	1.5
H&S/CO, MT/BN	6	54	60	.2	89.4	1611	843	.6	.2
MT/BN	35	607	642	1.8	853.5	36513	21785	9.4	8.1
VMO	8	29	37	.1	58.1	ND	730	2.5	.2*
RAD/INTELL/PLAT	1	44	45	.1	106.1	829	1115	.5	.1
ROCKET/DET:(PROV)	2	56	58	.2	49.6	2415	2318	1.0	45.0*
OTHER SERVICES									
COMM/UNIT NAVY	23	151	174	.5	136.4	ND	2665	2.0	[illegible]
CONST/BN NAVY	23	860	883	2.6	1375.0	ND	21111	13.3	4.5*
SPECIAL/CONST/BN NAVY	27	1411	1438	4.3	669.7	ND	3182	3.0	3.6*
MP/CO ARMY	5	114	149	.4	18.6	ND	514	.2	.1*
AMPHN/TRUCK/CO ARMY	7	162	169	.5	400.7	ND	13444	14.8	1.5*

SEE NOTES BEFORE USING CHART

*NOT BASED ON T/A ALLOWANCE OF WEAPONS, BUT ON AMOUNTS EMBARKED.

ND - NO DATA AVAILABLE

HQ/CO, H&S/BN	69	263	332	1.0	84.9	275	259	.2	.9
SER/CO, H&S/BN	8	140	148	.4	45.7	1226	150	.1	.4
MP/CO, H&S/BN	5	83	88	.3	15.0	267	153	.2	.3
TRAN/CO, H&S/BN	3	73	76	.2	168.8	13774	5017	3.0	2.3
BOMB/DISP/CO, H&S/BN	9	61	70	.2	84.0	1664	1779	1.8	.6
TOP/CO, H&S/BN	3	50	53	.1	37.0	1403	1034	.3	.7
H&S/BN	97	670	767	2.2	435.4	18609	8392	5.6	5.2
SIG/OPER/CO, SIG/BN	6	186	192	.6	76.5	1926	1673	.8	.5
SIG/CONST/CO, SIG/BN	5	165	170	.5	266.3	4286	3161	1.9	.4
HQ/CO, SIG/BN	34	305	339	1.0	371.0	9611	5104	3.1	1.1
SIG/BN	50	821	871	2.6	980.1	20109	13099	7.7	2.5
MED/CO, MED/BN	7	80	87	.3	132.6	1362	1261	.7	.1
H&S/CO, MED/BN	6	23	29	.1	51.0	598	209	.1	.1
MED/BN	27	263	290	1.0	448.8	4684	3992	2.2	.4
SHORE/BRIG, HQ/CO *	18	42	60	.2	122.3	C	2044	1.1	.3
HQ/BTY, CORPS/ARTY	27	194	221	.7	291.1	4887	5219	2.6	.3
FORCE UNITS									
20MM/BTY, L/AA/GRP	5	60	65	.2	36.7	1233	508	.2	2.8
40MM/BTY, L/AA/GRP	6	135	141	.4	120.0	3413	2902	1.1	12.0
GRP/HQ, L/AA/GRP	4	27	31	.1	31.6	685	752	.3	.1
L/AA/GRP	15	222	237	.7	188.3	5331	4162	1.6	14.9

SEE NOTES BEFORE USING CHART

* INCLUDES PERSONNEL OF HQ/SER/GRP.

UNIT	PERSONNEL			CARGO - SHORT TONS (FOR MEASURED TONS - SEE CONVERSION FACTORS IN NOTES)					
	OFFICER	ENLISTED	TOTAL	I	II & IV	SQ.FT. - VEH., GUNS, ETC.		III	V
DIVISION UNITS						ALLOW	EMBARK		
RIFLE/CO, I/BN	7	240	247	.7	27.6	99	99	.1	3.6
HQ/CO, I/BN	16	201	217	.7	38.8	742	887	.3	6.6
I/BN, I/RGT	37	919	956	2.9	121.6	1037	1184	.6	17.4
WPNS/CO, I/RGT	8	205	213	.6	174.7	3656	4258	2.1	16.6
H&S/CO, I/RGT	29	238	267	.8	87.1	1432	1671	.6	1.1
I/RGT	148	3200	3348	10.1	626.6	8199	9481	4.5	69.9
HOW/BTY, 105 HOW/BN	8	155	163	.5	78.1	2938	2510	1.0	39.6
H&S/BTY, 105 HOW/BN	16	166	182	.5	71.6	2607	2060	.8	1.2
105 HOW/BN, A/RGT	40	631	671	2.0	305.9	11421	9590	3.8	120.0
HOW/BTY, 155 HOW/BN	6	143	149	.4	188.5	3192	3225	1.9	55.6
H&S/BTY, 155 HOW/BN	16	145	161	.5	147.3	3031	3090	1.8	1.0
155 HOW/BN, A/RGT	34	574	608	1.8	712.7	12607	12765	7.5	167.8
H&S/BTY, A/RGT	25	203	228	.7	115.1	4842	3959	2.1	1.0
A/RGT	179	2670	2849	8.5	1745.5	51712	45494	21.0	528.8
E/CO, E/BN	6	192	198	.6	251.6	7776	4861	2.8	5.0
H&S/CO, E/BN	22	293	315	.9	1062.3	10835	10050	5.7	7.3
E/BN	40	869	909	2.7	1817.1	34163	24633	14.1	22.3
P/CO, P/BN	10	211	221	.7	235.8	4814	3274	3.2	2.1
H&S/CO, P/BN	14	127	141	.4	126.2	2432	1919	1.8	2.1
P/BN	44	760	804	2.5	833.6	16874	11741	11.4	8.4
TANK/CO, TANK/BN	7	161	168	.5	640.1	5972	5980	8.7	47.5
H&S/CO, TANK/BN	16	109	125	.4	194.	2997	3215	4.8	3.7
TANK/BN	37	592	629	1.9	2114.3	20913	21155	30.9	146.2
MED/CO, MED/BN	5	100	105	.3	58.3	1529	911	.5	.1
H&S/CO, MED/BN	23	65	88	.3	35.	1227	271	.2	.1
MED/BN, SER/TRPS	48	565	613	1.8	326.5	8872	4826	2.7	.6
ORD/CO, SER/BN	7	149	156	.5	63.3	7714	2965	1.4	25.0
SUP/CO, SER/BN	9	145	154	.5	92.5	510	356	.2	1.3
SER/CO, SER/BN	9	258	267	.7	57.3	1703	402	.2	1.1
HQ/CO, SER/BN	12	45	57	.2	8.1	280	0	.0	.2
SER/BN, SER/TRPS	37	597	634	1.9	221.2	10207	3723	1.8	27.6
TRUCK/CO, MT/BN	4	78	82	.2	149.6	7391	4297	1.9	1.6
AUTO/REP/CO, MT/BN	15	281	296	.9	201.6	6093	4642	1.4	1.9
H&S/CO, MT/BN	6	54	60	.2	89.4	1555	843	.6	.2
MT/BN, SER/TRPS	37	647	684	1.9	889.4	37212	22673	9.6	8.5
MP/CO, HQ/BN	7	114	121	.4	21.7	267	296	.2	.3
RECON/CO, HQ/BN	5	110	115	.3	17.5	0	0	.0	.7
SIG/CO, HQ/BN	17	282	299	.9	171.2	3693	3562	2.2	.7
HQ/CO, HQ/BN	79	385	465	1.4	191.4	3252	1803	1.1	1.0
ASSLT/SIG/CO, HQ/BN	55	430	485	1.5	89.5	5695	3118	1.8	1.4
WAR/DOG/PLAT, HQ/BN	1	68	69	.2	3.1	0	0	.0	.1
HQ/BN	164	1390	1554	4.7	494.4	12907	8779	5.3	4.2
MAR/DIV	1030	17690	18720	56.2	10321.8	217457	178802	110.3	956.3
CORPS UNITS									
HQ/CO, H&S/BN	69	263	332	1.0	84.9	275	259	.2	.9
SER/CO, H&S/BN	8	140	148	.4	45.7	1226	150	.1	.4
MP/CO, H&S/BN	5	83	88	.3	15.0	267	153	.2	.3
TRAN/CO, H&S/BN	3	73	76	.2	168.8	13774	5017	3.0	2.3
BOMB/DISP/CO, H&S/BN	9	61	70	.2	84.0	1664	1779	1.8	.6
TOP/CO, H&S/BN	3	50	53	.1	37.0	1403	1034	.3	.7
H&S/BN	97	670	767	2.2	435.4	18609	8392	5.6	5.2
SIG/OPER/CO, SIG/BN	6	186	192	.6	76.5	1926	1673	.8	.5
SIG/CONST/CO, SIG/BN	5	165	170	.5	266.3	4286	3161	1.9	.4
HQ/CO, SIG/BN	34	305	339	1.0	371.0	9611	5104	3.1	1.1
SIG/BN	50	821	871	2.6	980.1	20109	13099	7.7	2.5
MED/CO, MED/BN	7	80	87	.3	132.6	1362	1261	.7	.1
H&S/CO, MED/BN	6	23	29	.1	51.0	598	209	.1	.1
MED/BN	27	263	290	1.0	448.8	4684	3992	2.2	.4
SHORE/BRIG, HQ/CO *	18	42	60	.2	122.3	C	2044	1.1	.3
HQ/BTY, CORPS/ARTY	27	194	221	.7	291.1	4887	5219	2.6	.3
FORCE UNITS									
20MM/BTY, L/AA/GRP	5	60	65	.2	36.7	1233	508	.2	2.8
40MM/BTY, L/AA/GRP	6	135	141	.4	120.0	3413	2902	1.1	12.0
GRP/HQ, L/AA/GRP	4	27	31	.1	31.6	685	752	.3	.1
L/AA/GRP	15	222	237	.7	188.3	5331	4162	1.6	14.9

SEE NOTES BEFORE USING CHART

* INCLUDES PERSONNEL OF HQ/SER/GRP.

MARINE CORPS HISTORICAL LIBRARY
HQMC ROOM 3127

#166256628

Library of the Marine Corps

3000193703